

SAMPLE FINISH SCHEDULE

RETAIL FOOD FACILITIES

September 2026

ENVIRONMENTAL HEALTH



COUNTY OF LOS ANGELES
Public Health

ROOM NAME	FLOOR	COVER BASE 3/8" RADIUS	WALLS	CEILING
Service Area	Smooth quarry tile	4" quarry tile	Gypsum board; smooth; semi-gloss paint	Drop ceiling; vinyl faced panel; smooth;
Food Preparation area	Sealed smooth concrete	S3619T Slimfoot ceramic tile	Stainless steel	Drop ceiling; vinyl faced panel; smooth;
Utensil Washing area	Troweled epoxy monolithic floor - smooth	Continuous smooth epoxy flooring 4" up to the wall	Fiberglass Reinforced Panel (FRP);	Drop ceiling; vinyl faced panel; smooth;
Walk-in cooler	Prefabricated smooth sis floor	6" Stainless steel cove base	Smooth stainless steel	Smooth stainless steel
Food Storage Area	Smooth ceramic tile	4" ceramic tile	Smooth concrete wall; semi-gloss paint	Drop ceiling; vinyl faced panel; smooth;
Janitorial Area	Smooth ceramic tile	4" ceramic tile	Ceramic tile Smooth ceramic tiles, FRP, Gypsum board with semi- gloss paint	Drop ceiling; vinyl faced panel; smooth;
Restroom	Commercial Grade Sheet Vinyl (.050 inch wear layer thickness) + All seams welded or otherwise sealed to form a continuous surface	Continuous up to the walls, at least 4" forming an integral 3/8" minimum radius cove base	Smooth ceramic tiles, FRP, Gypsum board with semi- gloss paint	Drop ceiling; vinyl faced panel; smooth;